

15ft DNV 2.7-1 Certified Offshore Half Height Container



The Offshore Half Height Container has been designed, manufactured and certified in accordance with DNV 2.7-1. The units are supplied with certified slings and shackles as standard. All units are stackable where deck space or yard space is at a premium. The base has integrated forklift pockets for ease of yard loading and offloading. Our units can also be provided with a removable side wall to enable safe loading and unloading of materials or equipment. Internal tie down points throughout the interior provide strong points to secure cargo.

Brief Specifications

Dimensions	:	Length: 4.5M. Width: 2.5M. Height: 1.5M
Tare Weight	:	2960 KGs, 6525.6 lbs.
Payload	:	10,340 KGs, 22795.7 lbs.
Max Gross Weight	:	13,300 KGs, 29321.4 lbs.
Stacking	:	Units can be stacked with slings attached

Individual container dimension and weight may differ.

Designed, Fabricated, Tested and Marked in accordance with DNV 2.7-1, BS 12079

Includes DNV Certified Wire Rope Lifting Sling with Shackles.

All specifications are indicative, Individual container's dimension may differ

UAE	Dubai	Abu Dhabi	Jafza	Qatar	Doha	----- www.exeuae.com
	Dubai	Tel: +971 4 885 5336			Fax: +971 4 885 5582	Email: sales@exeuae.com
	Abu Dhabi	Tel: +971 2 554 4125			Fax: +971 2 556 8514	Email: auhsales@exeuae.com
	Qatar	Tel: +974 4 49878 49			Fax: +974 4 49 879 70	Email: sales@planetengg.com